

Public Information Meeting

Farmington Area Connectivity Study

Farmington, CT

Capitol Region Council of Governments



November 29, 2023



Presentation Outline

Project Background / History

Russell Arnold, Jr., PE
Public Works Director/Town
Engineer
Town of Farmington

Planning Study Introduction


Roger Krahn, PE, RSP1
Principal Transportation
Engineer
Capitol Region Council of
Governments

Planning Study & Progress


Kwesi Brown, PE, PTOE
Manager of Transportation
Engineering
SLR Consulting

Study Background/History- 1998 Plan






Bridge Location







2018 Concept Plan by AECOM

Monteith Bridge Rendering

2018 Concept Plans by AECOM







Monteith Bridge Rendering- 2018 Concept Plans by AECOM

Study Approach










Study to Date

- Stakeholder Engagement
- Traffic & Safety Data Collection
- Existing Conditions Analysis
- Future (2050) Traffic Conditions
 - No Build, Build, Existing Route 177 Bridge out of Service with New Bridge and without New Bridge
- Travel Time Runs (Oakridge Neighborhood)
- Traffic Impact Report (April 2023)






Stakeholder & Public Engagement

- Town of Farmington (Dec. 15, 2021)
 - Engineering, Board of Education & Emergency Services
- Adjacent Towns Planning and Engineering Staff (Nov. 18, 2021)
- Farmington Environmental Various Agencies (Dec. 16, 2021)
 - Lower Farmington River and Salmon Brook Wild & Scenic Committee
 - National Park Service
 - Farmington River Watershed Association
- CT Transit (Feb. 16, 2022)
- CTDOT Interagency Environmental Feb. 25, 2022
- Public Informational Meeting- Nov. 29, 2023



Traffic Data Collection

- Traffic Counts
 - 9/2021, 10/2021 and 1/2023
- Farmington Ave:
 - ADT: 16,500 Vehicles
 - Avg Speed: 43.4 mph
 - 85th Percentile Speed: 47.9
 mph
- New Britain Ave
 - ADT; 4,061 Vehicles
 - Avg Speed: 40.7 mph
 - 85th Percentile Speed: 46.4
 mph





Crash Analysis

- 2020 Capitol Regional Transportation Safety Plan
- CT Crash Data Repository
 - Crash Data within ½ mile radius of Proposed Bridge
- Farmington Avenue Intersections
 - 33 Total Crashes
 - 66% Property Damage
 - No Fatalities

Table 1 Farmington Avenue (Route 4) Crash Summary (2018-2021)

		CRASH EVERT					TYPE C	F COL	LISION			
LOCATION	PROPERTY DAMAGE ONLY	INJURY	TOTAL	REAR END	ANGLE	HIT ROADSIDE FIXED OBJECT	SIDESWIPE (SAME DIRECTION)	SIDESWIPE (OPPOSITE DIRECTION)	HEAD ON	HIT OBJECT IN ROADWAY	HIT PEDESTRIAN	TOTAL
		IN	TERSE	CTION:	5						383	
Route 4 at Walnut Street	0	1	1	1	0	0	0	0	0	0	0	1
Route 4 at Highwood Road	5	1	6	6	0	0	0	0	0	0	0	6
Route 4 at Monteith Drive	5	2	7	6	0	0	1	0	0	0	0	7
Route 4 at Knollwood Road	9	3	12	10	1	0	1	0	0	0	0	12
Route 4 at Wyndwood Road	3	4	7	3	1	1	1	0	1	0	0	7
Intersection Total	22	11	33	26	2	1	3	0	1	0	0	33
		RO	AD SE	SMENT	rs							
Walnut Street – Highwood Road	9	6	15	13	0	1	0	0	1	0	0	15
Highwood Road – Monteith Drive	9	2	11	6	1	1	0	0	1	2	0	11
Monteith Drive – Knollwood Road	9	4	13	5	2	2	1	2	0	0	1	13
Knoliwood Road – Wyndwood Road	7	1	8	6	0	1	0	0	0	1	0	8
Wyndwood Road – Trail Crossing	3	2	5	2	3	0	0	0	0	0	0	5
Segment Total	37	15	52	32	6	5	1	2	2	3	1	52

Source: Connecticut Crash Data Repository from January 1, 2018, to December 6, 2021.



Crash Analysis

- New Britain Avenue Intersections
 - 2 Total Crashes
 - All Property Damage
 - 1 Fatality between
 Oakridge and Roma Drive
 (Road departure crash)

Table 2 New Britain Avenue Crash Summary (2018-2021)


		CR/ SEVE	ASH RITY			TY	E OF (OLUS	ION	
LOCATION	PROPERTY DAMAGE ONLY	NUURY	FATAL	TOTAL	HIT ROAD SIDE FIXED OBJECT	AMGLE	HIT ANIMAL	REAR END	SIDESWIPE (SAME DIRECTION)	TOTAL
INTERS	стю	vs.								
New Britain Avenue at Haberern Avenue	1	0	0	1	0	0	0	1	0	1
New Britain Avenue at Oakridge	1	0	0	1	0	1	0	0	0	1
Intersection Total	2	0	0	2	0	1	0	1	0	2
ROAD SE	GMEN	ITS								
Haberern Avenue – Monteith Drive Extension (New Bridge)	3	0	0	3	2	1	0	0	0	3
Monteith Drive Extension – Oakridge	0	1	0	1	1	0	0	0	0	1
Oakridge – Roma Drive	4	2	1	7	5	0	1	0	1	7
Segment Total	7	3	1	11	8	1	1	0	1	11

Source: Connecticut Crash Data Repository from January 1, 2018, to December 6, 2021



Multi-modal facilities

- CT Transit
 - Routes 66 (local),Route 909 (express)
- Multi-Use Trails
 - Farmington River Trail
 - Farmington Canal Heritage Trail





Future Conditions Traffic Analysis

- Scenario 1: Future 2050 No Build With only the existing Route 177 Bridge in place
- Scenario 2: Future 2050 Build With both the existing and proposed Monteith Drive bridge in place
- Other Scenarios
 - Scenario 3: Future 2050 No Build with the existing Route
 177 Bridge out of service and without the proposed bridge
 - Scenario 4: Future 2050 Build with the existing Route 177
 Bridge out of service but with the proposed Monteith
 Bridge in place
- CRCOG's Travel Demand Model generated future volumes



	SERVICE CRITERIA INTERSECTIO MOTORIZED VEHICL	
LOS By Volume-t	o-Capacity Ratio ¹	CONTROL DEL AVAILA
v/c ≤ 1.0	v/c > 1.0	CONTROL DELAY (s/veh)
A	F	≤ 10
В	F	> 10 AND \le 20
C	F	> 20 AND \le 35
D	F	> 35 AND ≤ 55
E	F	> 55 AND ≤ 80
F	F	> 80



LEVEL-OF SERVICE CRITERIA	FOR TWSC INTERSECTIONS
LOS^1	CONTROL DELAY (s/veh)
A	≤ 10
В	> 10 AND ≤ 15
C	> 15 AND ≤ 25
D	> 25 AND ≤ 35
E	> 35 AND ≤ 50
F	> 50

Traffic Level of Service


Comparison of Future 2050 Conditions with and without Proposed Bridge

INTERSECTION/LANE GROUP	1	2050 SCENARIOS 1 & 2 (NO-BUILD AND BUILD CONDITIONS) LEVEL OF SERVICE						
INTERSECTION/DAME GROUP	A.M. PEA	K HOUR	P.M. PEAK HOUR					
	SCENARIO 1 (NO-BUILD)	SCENARIO 2 (BUILD)	SCENARIO 1 (NO-BUILD)	SCENARIO 2 (BUILD)				
Northbound Right	В	В	В	В				
Southbound Left/Through/Right	E	E	E	E				
Overall	В	В	В	В				
10: W Avon Rd (RT 167) & Sycamore Hills Rd	/Scoville Rd							
Eastbound Left/Through/Right	С	С	С	С				
Westbound Left/Through/Right	С	D	С	С				
Northbound Left/Through/Right	С	С	С	С				
Southbound Left/Through/Right	D	D	В	В				
Overall	D	D	С	С				
13: Stafford Ave & Stevens St	589	19 50		92				
Eastbound Left/Through/Right	С	С	С	С				
Westbound Left/Through/Right	С	С	С	С				
Northbound Left/Through/Right	Е	E	F	F				
Southbound Left/Through/Right	D	D	С	С				
Overall	D	D	F	F				
14: S Main St (RT 177) & Mill St								
Eastbound Left/Through	D	D	D	С				
Eastbound Right	С	С	С	В				
Westbound Left/Through	E	D	D	D				
Westbound Right	D	D	С	С				
Northbound Left	В	A	А	А				
Northbound Through/Right	В	A	Α	Α				
Southbound Left	В	В	В	A				
Southbound Through/Right	С	В	С	В				
Overall	С	В	В	В				
15: S Main St (RT 177) & Railroad Ave/New	Britain Ave							
Eastbound Left/Through/Right	D	D	D	С				
Westbound Left/Through	D	С	D	D				
Westbound Right	С	В	С	В				
Northbound Left	В	В	В	В				
Northbound Through/Right	С	В	С	В				
Southbound Left	С	A	С	A				
Southbound Through/Right	А	A	A	A				
Overall	В	В	С	В				
17: Plainville Ave (RT 177) & Coopermine Rd	ľ	1						





Traffic Level of Service





Analysis of Potential Neighborhood Impacts/Cut Through Traffic


- Trips to and from Proposed Bridge
 - Route 177 at Coppermine Road
 - Route 177 at West District Road
 - Red Oak Hill Road at New Britain
 Avenue
- Time of Runs
 - Peak (7-8 am) and Off Peak (2-3 pm)

Table 5 Traffic Routing Analysis

		7:00 -	8:00 A.M.	2:00 -	3:00 P.M.
Start/End Intersection		Time to travel to proposed bridge (minutes)	Time to travel away from proposed bridge (minutes)	Time to travel to proposed bridge (minutes)	Time to travel away from proposed bridge (minutes)
Plainville Avenue	Plainville Avenue and New Britain Avenue	4	5	5	5.5
(Route 177) at Coppermine Road	Coppermine Road and Oakridge	7.5	6	7.5	6.5
Plainville Avenue	Plainville Avenue and New Britain Avenue	3	4	4	4
(Route 177) at West District Road	West District Road and Oakridge	6	6	6	6
Red Oak Hill Road	New Britain Avenue	3	3	3	3
at New Britain Avenue	Red Oak Hill Road and Oakridge	8.5	7.5	8	7.5



Analysis of Potential Neighborhood Impacts/Cut Through Traffic






Preliminary Improvement Alternatives

- Preliminary Alternative 1
 - Roundabouts at Both Intersections
- Preliminary Alternative 2
 - Traffic Signalization at Both Intersections
- Preliminary Alternative 3
 - Roundabout at New Britain Avenue and Traffic Signal at Farmington Avenue

Preliminary Alternative 1

Roundabout
 Option


	SEVEL OF SERVICE							
INTERSECTION/LANE GROUP	A.M. PEA	(HOUN	P.M. PEAK	HOUN				
	DELAY (5)	LOS	DELAY (S)	LOS				
5: Farmington Ave (Rte 4) & New Br	idge							
Eastbound Left	9.0	A	4.6	A				
Eastbound Through/Right	25.1	D	23.4	C				
Westbound Left	8.9	A	6.5	A				
Westbound Through	12.6	В	11.5	В				
Westbound Right	0.0	A	0.0	A				
Northbound Left	11.8	В	10.2	В				
Northbound Through	32.2	D	12.0	В				
Northbound Right								
Southbound Left	10.0	A	9.4	A				
Southbound Through/Righ	9.9	A	10.0	A				
Overall	15.4	C	14.2	В				
30: New Britain Ave & New Bridge								
Eastbound Left/Thru	10.2	В	5.1	A				
Eastbound Through								
Westbound Thru/Right	7.9	A	8.8	A				
Westbound Right								
Southbound Left /Right	7.0	Δ	84	Δ				



Preliminary Alternative 2

 Traffic Signal Option


	Alternative 2 2050 SCENARIO 2 (BUILD CONDITIONS) LEVEL OF SERVICE								
INTERSECTION/LANE GROUP	A.M. PEAN	HOUR	P.M. PEAK HOUR						
	DELAY (5)	LOS	DELAY (S)	LOS					
5: Farmington Ave (Rte 4) & New Bridge									
Eastbound Left	13.8	В	8.7	A					
Eastbound Through/Right	42.3	D	54.9	D					
Westbound Left	35.3	D	39.7	D					
Westbound Through	24.0	C	19.3	В					
Westbound Right	10.3	В	0.8	A					
Northbound Left	44.4	D	44.2	D					
Northbound Through	38.6	D	33.2	c					
Northbound Right	7.9	A	7.2	A					
Southbound Left	41.6	D	33.5	c					
Southbound Through/Righ	44.3	D	45.3	D					
Overall	28.8	c	34.7	C					
30: New Britain Ave & New Bridge									
Eastbound Left	7.7	A	7.3	A					
Eastbound Through	8.6	A	6.6	A					
Westbound Through	13.2	В	14.3	В					
Westbound Right	7.4	A	5.3	A					
Southbound Left	28.9	C	18.6	В					
Southbound Right	6.3	A	4.8	A					
Overall	15.5	8	11.3	В					



Preliminary Alternative 3

 Roundabout -Signal Option

INTERSECTION/LANE GROUP	2050 SCENARIO 2 (BUILD CONDITIONS) LEVEL OF SERVICE							
INTERSECTION/LANE GROUP	A.M. PERI	HOUR	P.M. PEAK HOUR					
	DELAY (5)	LO5	DELAY (S)	LOS				
5: Farmington Ave (Rte 4) & New Bridge								
Eastbound Left	13.8	В	8.7	A				
Eastbound Through/Right	42.3	D	54.9	D				
Westbound Left	35.3	D	39.7	D				
Westbound Through	24.0	c	19.3	В				
Westbound Right	10.3	В	0.8	A				
Northbound Left	44.4	D	44.2	D				
Northbound Through	38.6	D	33.2	C				
Northbound Right	7.9	A	7.2	A				
Southbound Left	41.6	D	33.5	C				
Southbound Through/Righ	44.3	D	45.3	D				
Overall	28.8	C	34.7	C				
0: New Britain Ave & New Bridge								
Eastbound Left/Thru	10.2	В	5.1	A				
Eastbound Through				10.0				
Westbound Thru/Right	7.9	A	8.8	A				
Westbound Right	11000	10000						
Southbound Left/Right	7.0	A	8.4	A				
Southbound Right		10000						
Overall	8.1	A	8.4	A				





Findings

- Traffic Level of Service
 - LOS improvement on Route 177 corridor (Unionville)
 - LOS reduction in vicinity of proposed bridge
- Enhanced Connections between landmark facilities
 - Police station, senior center, high school, Town Hall, Library
- Bike Improvements
 - Multi-use trail along the river and connection to FCHT, bike lanes
- Potential New Bus Routes and Stops
- Neighborhood cut throughs not anticipated
- Quicker Emergency Response





Next Steps

- Selection of Preferred Improvement Alternative
- Final CRCOG Study Report
- Seek Project Funding
- Environmental Study
- Engineering/Design
- Construction



Questions/Comments

Study Documents on CRCOG Website

https://crcog.org/farmington-connectivity-study-2/

Russell Arnold, Jr., PE
Director of Public Works/Town Engineer
Town of Farmington
arnoldr@farmington-ct.org

Roger Krahn, PE, RSP1
Principal Transportation Engineer
Capitol Region Council Of Governments
rkrahn@crcog.org